

Schedule C

Name of work : Estimate for providing and fixing FRP sheet at terrace of Core lab Of PDPMIITDM Jabalpur

Sl.No	Dsr	Particulars of Item	Unit	Quantity	Rate (In figure & words)	Amount (In figure & words)
1	10.16	Structural steel work welded in built up sections, pipes tubes, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all and two coats of synthetic enamel paint complete.	Kg	475		
2	12.11	Extra for providing and fixing wind ties of 40x6mm flat iron section	Meter	60		
3	NS	Providing and fixing FRP sheet of 1.2mm thick corrugated sheets roofing and fixing with polymer coated J, or L hooks, bolts and nuts 8mm dia. G.I. plain and bitumen washers complete excluding the cost of purlins, rafters and trusses: corrugated sheets				
	a	Upto 60 degree pitch	Sqm	121		
4	21.1.1	Providing and fixing anotized aluminium flat fixed with expansion hold fasteners etc. the direction of the Engineer in charge	kg	37		
		Total			Rs.	