

### Schedule B

**Name of work : Aluminium partition in service block, office and AFM -STM lab PVC flooring in AFM-STM lab at Core Lab Complex.**

Sl.no.	DSR codes	Description	Unit	Quantity	Rate ( In figure & words)	Amount ( In figure & words)
1	21.1.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z section and other sections of approved make conforming to IS:733 and IS:1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and paneling to be paid for separately):				
		For fixed portion	Kg	400		
		Anodized aluminium (anodized transparent or dyed to required shade according to IS : 1868, Minimum anodic coating of grade AC 15)				
2	21.1	For shutters of doors, windows (including one side SS mosquito net) & ventilations including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Cost including Handle and Friction Stay)				
			Kg	50		
		Anodized aluminium (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)				

**Schedule B**

	21.3	Providing and fixing glazing in aluminium door, windows, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of the Engineer-in-Charge. (Cost of aluminium snap beading shall be paid in basic item).				
3	21.3.2	With float glass panes of 5.50mm thickness (weight not less than 13.75kg/ Sqm.).	sqm	15		
4	21.2.1	P/F 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 grade-1 typell in panelling fixed in aluminium doors ,windows shutter and partition frames with C.P. brass /stainless steel screws etc. complete as per architectural drawing and directions of Engineer -in-charge.				
		Prelaminated particle board with decorative lamination on one side and balancing on other side.	sqm	54		
5	6.11	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete.				
	6.11.1	200x10mm.	Each	7		
6	6	Providing and fixing aluminium handles ISI marked to required colour or shade with necessary screws etc. complete.	Each	12		
7	6.14	Providing and fixing aluminium hanging floor door stopper ISI marked anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade with necessary screws etc. complete.				

**Schedule B**

	6.14.1	Twin rubber stopper.	Each	7		
8	13.6	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade:				
	13.60.1	Two or more coats	sqm	90		
9	NS	P/F Aluminium door cill complete with all necessary screws.	mtr	2.7		
10	NS	P/F door lock of approved make (Godrej) complete with all necessary screws.	Each	6		
11	NS	P/F door closer of approved make (Godrej shakti) complete with all necessary screws.	Each	6		
12	NS	P/F PVC flooring of 1.5mm thick complete with all necessary requirements.	sqm	60		
		Total Amount				