

PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: Replacement of broken sheet of OTS roofing at Hall-3 of PDPMIIITDM Jabalpur

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
12.47	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I cost of purlins, rafters, trusses etc. The sheets shall be manufactured out plain/bitumen washers complete but excluding the of 2400 TEX panel roovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.				
12.47.2	2 mm thick flat	sqm	90		
Total Amount					