PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: Painting of facilities block and all toilets (only) of Hall of residence-1 of PDPMIIITDM Jabalpur.

				Rate	Amount
SI. No.	Description	Unit	Qty.	(In figure & words)	(In figure & words)
13.42	Distempering with 1st quality acrylic				
	washable distemper (ready made) of approved manufacturer and of required				
	shade and colour complete as per				
	manufacturer's specification.				
13.42.1	Two or more coats on new work.				
		Sqm.	2500		
13.8	Providing and applying white cement				
	based putty of average thickness 1mm, of approved brand and				
	manufacturer, over the plastered wall				
	surface to prepare the surface even and				
	smooth compelte.				
		Sqm.	120		
14.1	Repairs to plaster of thickness 12mmm				
	to 20mm in patches of area 2.5 sq. meters and under, including cutting the				
	patch in proper shape, raking out joints				
	and preparing and plastering the				
	surface of the wallls complete, including				
	disposal of rubbish to the dumping				
	ground within 50 meters lead:				
14.1.1	With cement mortar 1:4 (1 cement: 4				
	fine sand)	Sqm.	20		
14.5	Removing dry or oil bound				
	distemper,waterproofing cement paint,				
	exterior paints and the like by scraping ,sand papering and prepairing the				
	surface smooth including necessary				
	repairs to scratches etc. complete				
		Sqm.	2500		
14.5	Painting with synthetic enamel paint of				
	approved brand and manufacture to				
14 5 4 1	give an even shade :				
14.54.1	One or more coats on old work.	Sqm.	136		
Total Amount		1			