

PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: Providing of M.S. Tree guard (100 Nos.) at PDPM IIITDM Jabalpur.

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
10.25	Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel as required:				
10.25.2	In gradings, frames, guard bar, ladders, railings, brackets, gates and similar works.	Kg.	1800		
13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
13.61.1	Two or more coats on new work.	Sqmt.	310		
NS-1	P/F with M.S. framed of tree guard hard drawn steel wire febric 25x25 mm mesh of 10 gauge wire with required weld fix/bolt fix etc. complete as per direction of E-in-C.	Sqmt.	300		
Total					