

PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: Constructing connecting road with super Reflective interlocking concrete paver block between Hall-3 to Hall-4 .

Sl. No.	Description	Unit	Quantity	Rate (In figure & words)	Amount (In figure & words)
2.1	Earth work in surface excavation not exceeding 30cm in depth but exceeding 1.5 m in width as well as 10sqm on plan i/e disposal of surplus earth up to 50m and lift up to 1.5m, disposed soil to be levelled and neatly dressed.				
2.1.1	All kinds of soil.	Sqm	18		
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level				
4.1.10	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 50mm nominal size).	Cum	8.5		
4.4	Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centering, shuttering and finishing				
4.4.1	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	2		
5.9	Centering and shuttering including strutting, propping etc. and removal ofform for :				
5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	42		

Sl. No.	Description	Unit	Quantity	Rate (In figure & words)	Amount (In figure & words)
NS-2	P/F 60mm thick super reflective interlocked concrete block of approved size shape & colours manufactured approved by Engineer-in-charge with electro-hydraulically operated block making machine.The paver block shall be laid in approved pattern ,over 50mm thick compacted local stone dust (including cost of P/L stone dust) with 3mm thick joints filled with sand i/e levelling tamping & awEEPing etc. complete all as per direction of E-in-C .	Sqm	75		
Total Amount					