

PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: P/F granite on platform for sitting at Hall of Residence-III of PDPMIIITDM Jabalpur.

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
5.90	Centring and shuttering including strutting, propping etc. and removal of form for :				
5.9.3	Suspended floors, roofs,landings balconies etc.	Sqm.	10		
5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
5.22.6	TMT bars.	Kg.	60		
5.10	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring,shuttering,finishing and reinforcement - All work upto plinth				
5.1.2	1:1.5:3 (1 cement:1.5 coarse sand:3 graded stone aggregate 20mm nominal size)	Cum.	1		
6.10	Brick work with F.P.S. bricks of 35 designation in foundation and plinth in :				
6.1.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	2.5		
8.20	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, windowsills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4coarse sand), joints treated with white cement, mixed with matching pigment,epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
8.22	Granite of any colour and shade				

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
8.2.2.2	Area of slab over 0.50 sqm	Sqm.	31		
13.40	12 mm cement plaster of mix :				
13.4.2	1:6 (1 cement : 6 coarse sand)	Sqm.	20		
13.80	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth compelte.	Sqm.	20		
13.46	Finishing walls with Premium Acrylic Smooth exterior paint with silicon additiv of required shade				
13.46.1	New work (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including priming coat of exterior primer applied @2.20 kg/10sqm).	Sqm.	20		
Total Amount					