

PDPM IIITDM JABALPUR

Schedule of Quantities

Name of work: Repairing of boundary wall at IIITDM Jabalpur.

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
2.8	Earth work in excavation by mechanical means (hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width 10 sqm on plan), including dressing of side and ramming of bottom, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.				
2.8.1	All kinds of soil	Cum.	6.1		
6.1	Brick work with common burnt clay FPS (non modular) bricks of class designation 35 in foundation and plinth in:				
6.1.2	Cement mortar 1:6 (1 Cement :6 coarse sand)	Cum.	30		
6.4	Brick work with common burnt clay FPS (non modular) bricks of class designation 35 in superstructure above plinth level up to V level in all shape and sizes in:				
6.4.2	Cement Mortar 1:6 (1 Cement :6 coarse sand)	Cum.	6		
	Cement plaster (in coarse sand)				
13.4	12mm cement plaster of mix:				
13.4.2	1:6 (1 cement : 6 coarse sand)	Sqm.	75		
13.5	15 mm cement plaster on rough side of single or half brick wall of mix :				
13.5.2	1:6 (1 cement: 6 coarse sand)	Sqm.	70		
Total					