

PDPM IITDM JABALPUR

Schedule of Quantities

Name of work: Removing of existing urinol sensor and fixing of Manual urinol flush for Hall of Residence -III.

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete	Sqm	50		
15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm.	50		
18.70	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge				
18.7.2	20 mm nominal outer dia Pipes	Meter	166		
Ns-1	P/F of Auto closing flush volve with necessary fittings etc. complete	Nos	111		
Total Amount					