

# PDPM IIITDM JABALPUR

## Schedule of Quantities

**Name of work: Providing of chain link fencing for Volleyball Court at IIITDM Jabalpur.**

Sl. No.	Description	Unit	Qty.	Rate (In figure & words)	Amount (In figure & words)
2.30	Excavation holes more than 0.10 cum & up to 0.5 cum including getting out the excavated soil, than returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by remming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 met. and lift up to 1.5 met.				
2.30.1	All kinf of soil	Each	37		
4.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.4	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum.	5		
10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
10.25.2	In gratings, frames, guard bar , ladder , railings, bracket s, gates and similar works.	Kg.	375		
13.61	Painting with synthetic enamel paint of approved brand and manufacture to give and even shade:				
13.61.1	Two or more coats on new work.	Sqm.	38.64		
16.7	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of				
16.70.1	Made of G.I. wire of dia 4mm	Sqm.	322		
<b>Total Amount</b>					