## Schedule of Quantity-A

Name of work: Providing and Fixing Carpet in 600 capacity lecture hall in LHTC building.

| Item No. | Description of items                     | Unit  | Quantity   | Rate | Amount |  |
|----------|--|-------|------------|------|--------|--|
| NS-1     | Providing and fixing of 7 mm thick (with |       |            |      |        |  |
|          | cut pile) Carpet of approved brand and   |       |            |      |        |  |
|          | made of wooven Polypropylene yarn        |       |            |      |        |  |
|          | with pile weight 825 - 875 gm/sqm,       |       |            |      |        |  |
|          | minimum total weight 1650 gm/sqm         |       |            |      |        |  |
|          | with primary backing and confimity       |       |            |      |        |  |
|          | against pill test etc. complete as per   |       |            |      |        |  |
|          | direction of Engineer-In-Charge.         |       |            |      |        |  |
|          |  | Sqft. | 4900 Sqft. |      |        |  |
|          | Total                                    |       |            |      |        |  |

Rate to be inclusive of taxes and FOR at Institute site

(Signature of contractor)