

Schedule of Quantity

Name of work: Providing & Fixing granite on sitting platform at Aryabhata Hostel (Hall-3).

DSR No.	Description of items	Unit	Quantity	Rate	Amount
8	CLADDING WORK				
8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
8.2.2	Granite stone slab colour black, Cherry/Ruby red				
8.2.2.2	Area of slab over 0.50 sqm	90	sqm	4425.35	398282.00
Total Amount					398282.00

Quoted Rates:% above / below estimated cost
(To be quoted by the contractor)

(Signature of contractor)