

Schedule of Quantity

Name of work: C/o. Boundary wall with MS structure at nala near Primary Health Centre of PDPMIITDM Jabalpur.

DSR No.	Description of items	Unit	Quantity	Rate	Amount
4	CONCRETE WORK				
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.2	1:1½:3 (1 Cement: 1½ coarse sand (zone III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	3	Cum.	7210.55	21632.00
10	STEEL WORK				
10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3720	Kg.	101.75	378510.00
23	RAIN WATER HARVESTING & TUBEWELLS				
23.1	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level.				
23.1.2	Rocky strata including Boulders				
23.1.2.1	up to 300 mm dia	32	Mtr.	1223.20	39142.00
Grand Total Amount					439284.00
Say Total Amount					439300.00

Quoted Rates:% above / below estimated cost
(To be quoted by the contractor)

(Signature of contractor)