

## Schedule of Quantity

**Name of work: Providing & Fixing granite wall lining at the side of opening of lift  
at Maa Saraswati Hostel & Panini Hostel (Block-B) at IIITDM  
Jabalpur.**

DSR No.	Description of items	Unit	Quantity	Rate	Amount
NS-1	Providing and fixing 16 to 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for wall lining (veneer work) backing filled with grout of average 12 mm thick in cement mortar 1;3 (1 cement : 3 c. sand) including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the shade. (To be secured the backing by means of cramp/dash fasteners)				
	Granite of any colour and shade	105	sqm	4496.50	472132.50
<b>Total Amount</b>					<b>472132.50</b>
<b>Say</b>					<b>472150.00</b>

**Quoted Rates:** .....% above / below estimated cost  
(To be quoted by the contractor)

(Signature of contractor)