Name: Repairing and servicing of 11KV HT panel installed at Power house.

SI No.	Description	Unit	Qty	Rate	Amount	Remark
	fixing of spouts including Servicing,					
	overhauling ,oilling, greasing with					
	protection sutter, repair of damage					
	control wiring, removing and testing of					
_	11KV HT switch.	job	16			
2	Supply and fixing of SS nut bolt	each	100			
	Supply and fixing of HT 11KV grade					
3	insulation sleeves 50mm	mtr	30			
4	Supply and fixing of space heater	each	24			
	Repairing and servicing of indoor VCB					
	breaker including greasing,					
	checking/cleaning of primary secondry					
	circuits,					
	testing/synchronising/callibration of					
	inside relays/display, meter etc.					
	complete as per instruction of engineer-					
5	in-charge.(Make:ABB)	each	8		_	
	Callibration and testing of over current					
	and earth fault relay fixed above HT					
6	panel by primary ejection method.	each	8			
	Repairing of door locking.	each	6			
	Repair / Replacement of LED indicator	each	16			
9	Replacement of TNC switch.	each	8			
10	Labour charge	Job	1			
	Total					
	Add GST @ 18%					
	Grand total					